1 01111 1 (011 E1181 (1814) 1 (07 10 18	1 01111 Tte V. 1 (0)	01		Bireeti te de	110. 01.0 1.2007
SOP No.	RMM/SOP/GEN/01	Effective Date	01. 11.2013	REVISION No	04
SOP DESC	TRANSPORTING OF ANY RAW MATERIAL.	Section	GENERAL		
DEPARTMENT	RAW MATERIAL MANAGEMENT	Page	1 of 6		

Step No.	Activity (WHAT)	Associated Requirements/Hazards/Impacts	Responsibility (WHO)	Process / tools / PPEs (HOW)	Remarks / Reference
	Before starting of the Job	 SAFETY: Unawareness about the hazard prevailing in that area. Injury due to starting the equipment of others. Injury due to starting of equipment which is not in healthy condition. Injury due to unawareness about the job Unawareness about the safety standard Injury due to no use of PPEs. 	Contractor supervisor/ Foreman/Shift Sr.Incharge	 Brief about the hazards before starting of the job. Maintain a equipment allocation register. Operator must carry starting key along with him. Maintain a equipment status register Check the equipment as per check list and operate only when it is in healthy condition. Only trained person should be deployed in the job. Check whether that person is trained or not by seeing training record. Must know the role of others in that area. Training of Road Transportation safety standard. Use PPEs. 	Awareness of following safety standard is required:- Road: SS/GEN-12 Rail: SS/GEN-24 Loose Clothing: SS/GEN-2 EYE: SS/GEN-6,7 HEAD: SS/GEN-7 Transportation:SS/GEN-29. At all loading and unloading point supervisor must be present.
		ENVIRONMENT:			
		QUALITY:			

PREPARED BY	APPROVED BY
Name and Desig.: Varun Kumar , Asst Manager	Name and Desig.: Prakash Singh, Chief RMM
Signature with Date: Laurelle 39 10 2013	Bakash Songh
Signature with Date: 28.10.2013	Signature with Date: 30.10.2013

1 01111 110 E1101110111/ 110/ 1013	1 of the vertices	01		Directive at	110. 01.0 1.2007
SOP No.	RMM/SOP/GEN/01	Effective Date	01. 11.2013	REVISION No	04
SOP DESC	TRANSPORTING OF ANY RAW MATERIAL.	Section	GENERAL		
DEPARTMENT	RAW MATERIAL MANAGEMENT	Page	2 of 6		

Step No.	Activity (WHAT)	Associated Requirements/Hazards/Impacts	Responsibility (WHO)	Process / tools / PPEs (HOW)	Remarks / Reference
2	Loading of raw material	 SAFETY: Injury to driver during loading. Hit by dumper and loading equipments Injury due to collapse of heap during cutting of heap. Collision between dumper and loading equipment. Toppling of dumper due to loading on the rear side. Injury due to falling material from the Bunker. 	Contractor supervisor / Driver / Operator/Helper	 <u>Dumper driver should not come down</u> from his cabin during loading. 	USE of PPE is must when driver and operator is outside of the cabin
		ENVIRONMENT: Spillage	Contractor supervisor / Driver / Operator/Helper		

PREPARED BY	APPROVED BY
Name and Desig.: Varun Kumar , Asst Manager	Name and Desig.: Prakash Singh, Chief RMM
Signature with Date: Laurelle 39 10 2013	Bakash Songh
Signature with Date: 28.10.2013	Signature with Date: 30.10.2013

1 01111 1 (01) 21121 1 21121 1 (01)	1 01111 110 11 1	0.1. 0.1		Bireen te de	ace: 01:01:2007
SOP No.	RMM/SOP/GEN/01	Effective Date	01. 11.2013	REVISION No	04
SOP DESC	TRANSPORTING OF ANY RAW MATERIAL.	Section	GENERAL		
DEPARTMENT	RAW MATERIAL MANAGEMENT	Page	3 of 6		

Step No.	Activity (WHAT)	Associated Requirements/Hazards/Impacts	Responsibility (WHO)	Process / tools / PPEs (HOW)	Remarks / Reference
				 Do not over full the dumper and shut the gate completely Vehicle dala must be covered through mechanized covering system to avoid moisture and pollution during transit. 	
		QUALITY: Loading of wrong material.		 Take instruction from concerned person. 	
3	Transporting	 SAFETY: Collision with other s on the road. Collision with wagon /Loco and Drop gate. Hit during reversing Spillage from vehicle Entangling or fauling of dala against the structure. 	Contractor supervisor / Driver / Operator	 Check vehicle as per checklist. Follow Transportation Safety standards. Follow Road Safety standards. Follow defensive driving Follow transportation Safety Standards. Helper less driving. Stop, look and Go at any level crossing. Follow Rail Safety Standard. During reverse, must ensure that reverse buzzer is ON. Use three piece mirrors. 	 Max speed of vehicle is 35KPH at main road and 16 KPH at branch road. Donot ply vehicle during safety time.

Prakash Singh, Chief RMM	
Name and Desig.: Prakash Singh, Chief RMM	
Bakesh Songh 30.10.2013	

1 01111 110 E1151115111/ 110/ 101.	1 01111 100 1110	01		Directive at	110. 01.01.2007
SOP No.	RMM/SOP/GEN/01	Effective Date	01. 11.2013	REVISION No	04
SOP DESC	TRANSPORTING OF ANY RAW MATERIAL.	Section	GENERAL		
DEPARTMENT	RAW MATERIAL MANAGEMENT	Page	4 of 6		

Step No.	Activity (WHAT)	Associated Requirements/Hazards/Impacts	Responsibility (WHO)	Process / tools / PPEs (HOW)	Remarks / Reference
		ENVIRONMENT:	Contractor	 Ensure Dala is in proper condition. Ensure dala door is properly clamped /locked. Do not move vehicle in raised Dala or boom condition. Ensure hoisting device interlock system is not bypassed. 	
		 Pollution due to smoke emission. Sound pollution QUALITY: 	Contractor supervisor/ Driver/Operator	Regular check up of vehicle as per norms	
4	Unloading of raw material.	 SAFETY: Hit by dumper during placement of dumper at unloading point Damage to dumper. Hand injury during operation of dala door hook. Toppling of dumper during hoisting Toppling of equipment from height during unloading in the heap. 	Contractor supervisor / Driver /Helper	dumper. • Helper should go for open the dala	USE of PPE is must when driver and operator is outside of the cabin

PREPARED BY	APPROVED BY
Name and Desig.: Varun Kumar , Asst Manager	Name and Desig.: Prakash Singh, Chief RMM
Signature with Date: Laurelle 39 10 2013	Bakash Songh
Signature with Date: 28.10.2013	Signature with Date: 30.10.2013

1 01111 1 (011 21181/181/17 1 10/1018	1 01111 Tte V. 1 (0)	. 01		Bireeti te de	10. 01.0 1.2007
SOP No.	RMM/SOP/GEN/01	Effective Date	01. 11.2013	REVISION No	04
SOP DESC	TRANSPORTING OF ANY RAW MATERIAL.	Section	GENERAL		
DEPARTMENT	RAW MATERIAL MANAGEMENT	Page	5 of 6		

Step No.	Activity (WHAT)	Associated Requirements/Hazards/Impacts	Responsibility (WHO)	Process / tools / PPEs (HOW)	Remarks / Reference
				 signal to be given to the driver's for unloading materials Maintain safe distance from the dumper. Place dumper at the marked place Have proper communication with helper. During reversing use reverse buzzer and use three piece mirrors. Do not dump over the heap. Use proper tool for opening lock. Wear hand gloves. Start hoisting only after applying hand brake and ensure that dumper is in still condition. Mark the area of unloading. Do not unload in downward direction. 	
		ENVIRONMENT: Dust pollution.	Contractor supervisor / Driver /Helper	Use dusk mask	
		QUALITY: Mix up of material	Contractor supervisor / Driver	Donot unload over other material.	

PREPARED BY	APPROVED BY		
Name and Desig.: Varun Kumar , Asst Manager	Name and Desig.: Prakash Singh, Chief RMM		
Signature with Date: Lauther 29 10 2013	Bakash Songh		
Signature with Date: 28.10.2013	Signature with Date: 30.10.2013		

SOP No.	RMM/SOP/GEN/01	Effective Date	01. 11.2013	REVISION No	04
SOP DESC	TRANSPORTING OF ANY RAW MATERIAL.	Section	GENERAL		
DEPARTMENT	RAW MATERIAL MANAGEMENT	Page	6 of 6		

Step No.	Activity (WHAT)	Associated Requirements/Hazards/Impacts	Responsibility (WHO)	Process / tools / PPEs (HOW)	Remarks / Reference
			/Helper		
	Parking of Vehicle	SAFETY: Roll down of vehicle	Driver	 Apply parking break . Park in a plain surface. Put scotch block. Park only in parking place. 	
		ENVIRONMENT:		•	

PREPARED BY	APPROVED BY
Name and Desig.: Varun Kumar , Asst Manager	Name and Desig.: Prakash Singh, Chief RMM
	0
Signature with Date: 28.10.2013	Signature with Date: 30.10.2013